



CUSTOMER - APV AMERICAS/FRICK CO.
 JOB - APV SYSTEMS
 LOCATION - BOISE, ID.
 QUANTITY - (2) RIGHT HAND UNITS
 NET WEIGHT - 6,471 LBS. W/CURB SECTION
 CAPACITY - 9.5 TONS AT 10F TD / -20F ET
 REFRIG. - PUMP RECIRC R-717 (3:1 RATE)

DEFROST - HOT GAS
 COIL - STEEL TUBES & FINS (HDG)
 CHARGE - 4.65 CU. FT. INT. VOL.
 AIR FLOW - 15,720 CFM
 FANS (1) - 36" DIA. PROP. TYPE
 MOTORS (1) - 5 HP/1160 RPM
 480/60/3 T.E.F.C.

MARK -

- NOTES:
1. UNIT TO BE SHIPPED IN (2) PCS.
 2. 18" INSULATED STEEL CURB. (SEE DWG. 106570-5-1).
 3. RIGHT HAND UNIT SHOWN (LEFT HAND UNIT OPPOSITE)
 4. VELOCITY THRU COILS = 786 FPM
 5. COIL FACE AREA = 20.0 SQ.FT.
 6. ORIFICE FEED: 1.7 GPM LIQUID IS REQUIRED AT MINIMUM 1.3 PSI ABOVE COIL SUCTION PRESSURE AT LIQUID INLET.

DO NOT SCALE PRINT WORK TO DIMENSIONS

CUSTOMER P.O. 0600013551		FRICK NO. 213553	
S.D. 30850A	SHEET		OF
DATE 1/25/01	SCALE NONE	NO. REVD. NOTED	
DRAWN BY [Signature]	CHECK BY	APPROV BY	
TITLE			
ROOF TOP FREEZER			
REVISOR		DATE	BY
FRIGID COIL		MODEL RTFS-L-201-103-5-LRB HGU-IP-PCV 20 P	DRAWING NO. 939650AR
			REV A